DAVANGERE TOWN MUNICIPALITY.

Notice is hereby given that sealed tenders will be received in the office of the President, Davangere Municipality up to 1st October 1926, for carrying out the Drainage Scheme at Davangere Town commencing from the year 1926-27, and extending over for five years up to 1930-31.

2. The approximate quantity and description of the work required to be done are given in the sub-joined statement and tenders should be sent in the form of that statement duly noting in the column left blank, the rates at which each item of work will be executed. The tender should be superscribed "Tender for the Drainage Scheme at Davangere" in default of which tenders will be rejected.

3. Earnest money of Rs. 2,000 which should be in cash or currency notes or by means of cheques on the Mysore Bank, Davangere, should accompany the tender, without which, tenders will not be considered.

4. The rates offered should include the cost of materials and the charges for complete construction of the said drains, etc., at Davangere and should hold good throughout the years 1926-27, up to end of 1930-31. No application from the contractor for any sort of concession owing to the rise in prices of materials or any other cause will be considered.

5. The plans and detailed estimates may be seen at the Office of the President, Davangere Municipality, between the hours of 12 NOON and 5 P.M. on all working days.

6. The final acceptance of any tender will rest with the Municipal Council, Davangere, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract Bond on stamped paper, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

8. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. On acceptance of one of the tenders, the earnest money on rejected tenders will be refunded.

10. Charges on account of implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne entirely by the contractor.

11. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Municipality or those fixed by the Municipal Council after working out data, with not more than ten per cent for contractor's profit.

12. In all matters not specially provided for, and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the *Municipal Council, Davangere*, will be final and legally binding.

13. The value of the work to be turned out each calendar month shall not be less than Rs. 1,500. Progress of work will be reckoned from the date of agreement.

Description of work	Unit	Quantity	Rate
1. Constructing conservancy drains for streets wherever actually found necessary—			
3" Radius	R.ft.	15,280	
4" (1)	"	1,095	
4" (2)	"	965	
2. Constructing storm water sub-mains and main-drains, Silk's Pattern—			
3" Radius	"	3,780	
4" do (1)	"	1,165	
4" do (2)	"	1,235	
5" do (3)	"	1,020	
5" do (4)	"	1,250	
6" do (5)	"	470	
6" do (6)	"	790	
6" do (7)	"	475	
7" do (8)	"	320	
7" do (9)	"	360	
11" do (10)	"	640	
3. Improving the existing "V" drain with concrete and cement plastering; to invert and pointing with cement to joints of slabs	R.ft. 100	390·96	

Description of work	Unit	Quantity	Rate
4. Removing completely and relaying the existing "V" drains with concrete for the invert and cement plastering and pointing to joints of slabs	R.ft. 100	25·55	
5. Repairing the existing slabbed trough drains with cement pointing to sides and floor ...	R.ft. 100	34·80	
6. Dismantling existing damaged conservancy drains and reconstructing Silk Pattern 3" conservancy drains	R.ft.	1,890	
7. Removing the existing "V" slabs and reconstructing as 3" storm water drains, complete, using old slabs ...	"	575	
8 Raising the sides of drains with burnt stones in clay and pointing in mortar	"	3,080	
9. Improving the existing earthern main drain with burnt stone slab flooring to bed and 3" concrete drain in centre and revetment to sides utilizing old stones at site for 33 per cent of the work	"	1,350	
10. Concreting the floor of the existing masonry trough drains and curving the edges and plastering with cement and pointing the sides and top	"	2,219	
11. Constructing new tunnels of different sizes, tunnel of 1 vent—			
2 x 2 36 feet long	Each	4	
Do 24 do	"	11	
Do 20 do	"	8	
Do 15 do	"	18	
12. Reparing the existing old tunnel, removing and relaying the existing slabs with pointing and silt clearing—			
Tunnels of 20 feet long	No.	47	
Do 15 do	"	18	
13. Constructing masonry parapets and pointing with mortor for the existing tunnels	"	12	
14. Gravelling over the tunnels, new and old, including collecting, carting, stacking and spreading gravel and consolidation	"	106	
15. Storm overflows along main intercepting drains at junctions of drains as per discharge statement	"	10	
16. Constructing underground stoneware pipe sewers from Kaipet road west end to north of Honda, excavation, cutting, and refilling gravelly soil and soft rock.....Cubic feet	100	196·20	
9" Stoneware pipe	R.ft.	1,071	
Laying and jointing 9" pipe	"	1,050	
17. Constructing junction manholes—			
Do 4 x 4 x 5	No.	1	
Do 4 x 4 x 6	"	1	
Do 4 x 4 x 7	"	1	
Do Inlet cistern	"	1	
Do Outlet cistern	"	1	
19. Drops along drains in west side of Anajee road	...	7	
20. Dismantling houses and removing debris to a distance of half a mile	Ankanam	28	

CHARLES NORONHA,
President.

TUMKUR DISTRICT.

TALUK BOARD OFFICE, KORATAGERE.

Notification dated 4th August 1926.

It is proposed to hold a weekly shandy every Saturday near Sri Anjaneyaswami Temple at Kyamenahalli of this Sub-Taluk, persons having any objections to the above proposal may intimate the same in writing to the undersigned within three months from the date of publication of this notification, failing which, no objections will be entertained after the due date.

A. N. ANANTARAMAIYA,
President.